



WINDOW SCHEDULE:

- A. TIMBER FRAMED DOUBLE HUNG
850w. X 1500h.
- B. TIMBER FRAMED DOUBLE HUNG
380w. X 1500h.
- C. ALUMINIUM FRAMED FIXED GLASS
550w. X 950h.
- D. ALUMINIUM FRAMED LOUVER
550w. X 550h.
- E. ALUMINIUM FRAMED LOUVER
440w. X 1200h.
- F. ALUMINIUM FRAMED LOUVER
540w. X 1150h.

WITH COMPLIMENTS FROM:
MACKAY & SONS HOUSE REMOVALS

www.houseremovals.com.au
PH. (07) 3888 9399
FAX. (07) 3888 9344

CEILINGS : 3200 PINE VJ & FIBRE CEMENT.
FLOORING : 140x19 PINE & 90x19 HWD.
WALLS : PINE VJ & FIBRE CEMENT

NOTES:

REFER BRACING PLAN FOR SITE SPECIFIC STRUCTURAL UPGRADING REQUIREMENTS
BUILDING DIMENSIONS, CONDITIONS AND MATERIALS INDICATIVE ONLY, OWNER/CONTRACTOR TO CONFIRM BEFORE COMMENCEMENT.
ALL DIMENSIONS ROUNDED TO NEAREST 100MM.

**LIVING AREA 116m.²
COMBINED VERANDAH AND DECK AREA 33m.²**